

Mandatory Visit Q & A (update Nov 19, 2024)

Q. is this an all or nothing bid?

A. Yes

Q. How many strands of fiber

A. 6

Q. what are the fiber distances

A. You can measure for yourself as i walk you to each location

Q. Is there any fiber work to do at the High school campus?

A. NO.

Q. You have all Aruba now?

A. YES

Q. for the projects at high school to remove racks/pull copper, do you have those labeled or will i have to identify them myself?

A. You will have to tone them out. And then pull wire to the appropriate existing rack and punch them down. For about 25 wires. (some desktops, (i.e. keystones on wall) and some wireless (i.e. ceiling drops to existing and new APs

Q. How do i know where to pull the new Wireless drops

A. The new maps on the wall. Green is new, blue is existing.

Q. Will you produce a map for us that is like what's on the wall

A. Yes, stay tuned to 470/CRW for those digitized documents later this week.

Q. How will i identify the rack to pull the new wireless drops to?

A. You will pull to the nearest rack that remains. See drawings, the red box is a rack.

Q. Do you require a certain color of Plenum rated Cat 6?

A. Yes, yellow for wireless, blue for wired

Q. Will you let us put our 1u fiber enclosure in your rack?

A. Yes, it was agreed in the walkthrough that all vendors planned to install their own fiber equipment

Q. Is there a rack everywhere?

A. No, in the Middle School Laundry, the equipment is all mounted on the wall, no room is available for a rack. You must plan to mount that on a block wall.

Q. Do we take down the retired racks in 1100c and 1105?

A. Yes.

Q. Do we remove the old wire?

A. Yes, Copper only.

Q. can you print that? (my notes were onscreen)

A. Sure.

Form 470

1. Part 1 - Wireless gaps filled at all campus
 - a. 109 Wire Pulls
 - b. 89 APs (we have 20 to use in our reserve now)
 - c. 7 6300L Switches to power APs at all campus, (HS is done, but will buy 6300L's and then trade 3 M's from HS (any edge device) to MS,IS,PS to provide an M at all 4 campus MDFs
2. Part 2 - Fiber pulled inside PS IS MS for 10GB to every rack
 - a. PS 1 pull from Office to K Workroom
 - b. IS 1 pull from Library to Custodial Closet rack
 - c. MS 3 fiber pulls
 - i. Library (MDF) to Office
 - ii. Library to Laundry Rack
 - iii. Library to F Hall Rack