

Summary

Description	Qty
Ports Need Terminated in Closet	1997
Ports Need Terminated in Classrooms, Offices, Etc.	971
24 Port Patch Panel w/ Inserts	46
48 Port Patch Panel w/ Inserts	31
6-inch Cat6 Patch Cable	1600
1ft Cat6 Patch Cable	350
3ft Cat6 Patch Cable	125
Wall Cat6 Jack Inserts	971
Wall Plates w/ Single Inserts	700
Wall Plates w/ Dual Inserts	150
12u Wall Mount Rack, 20" depth (swing gate, opens from back)	3

Termination Breakdown by IDF/MDF

School	Closet	Ports Need Terminated in Closet	Ports Need Terminated on opposite End	24 Patch Panels	48 Patch Panel
ACA	MDF	128	65	0	0
APO	145-MDF	12	0	1	2
APO	110	0	0	0	0
APO	181	0	0	0	0
CDS	CAFE	0	0	0	0
CDS	39	43	18	2	0
CDS	4C	74	30	2	1
CDS	27-MDF	78	46	2	1
CHA	PAT	0	0	0	0
CHA	18	59	25	2	1
CHA	LIB	104	43	2	2
CHA	58	87	55	2	1
CHA	PS	18	13	2	0
DIS	111	0	0	0	0
DIS	126	64	34	1	1
DIS	105-MDF	64	35	1	1
EAR	WR	0	0	0	0
EAR	Library-MDF	127	42	1	3
EHS	231	12	0	1	0
EHS	143	12	0	0	0

EHS	Counselor	0	0	0	0
EHS	GYM	0	0	0	0
EHS	TIES	0	0	0	0
EMS	TR1	0	0	0	0
EMS	DC	0	0	0	0
EMS	TR2	0	0	0	0
EMS	Stadium	0	0	0	0
EXP	Multi	0	0	0	0
EXP	520	40	18	1	1
EXP	Office	55	26	1	1
EXP	MDF	110	61	1	2
EXP	BBallField	0	0	0	0
GHS	C31-1stBase	166	111	2	3
GHS	H21-Gym	35	0	2	0
GHS	J45-Mezz	63	28	1	1
GHS	D05-3rdBase	81	30	2	1
GHS	2ndBase	83	51	2	1
GHS	Library-MDF	55	16	0	1
GHS	Visitor-Conc	7	4	1	0
GHS	FieldHouse	12	7	1	0
GHS	Concessions	21	15	2	0
GMS	E2	0	0	0	0
GMS	A27	55	24	1	1
GMS	Library-MDF	138	74	4	3
OAK	LIB	0	0	0	0
OAK	129	76	40	2	1
OAK	MEZZ-MDF	105	55	3	2
SD	Rm4	13	5	1	0
Totals		1997	971	46	31