Scope of work at LaCrosse High School:

New data cables will need to be run from the following rooms to the new IT room C114:

- Classrooms 109 113 and classroom 117.
  - 4 network lines in classrooms 109, 110, 111, and 113.
  - 2 network lines in classrooms 112 and 117.
  - $\circ~$  All data cables will be ran to the new IT room C114.
- Classrooms 105 108
  - Existing data cables will need to moved from the current IT room to the new IT room C114.
- Classrooms C105 C107 and C111
  - $\circ$  All data cables will need to be ran to the MDF in the new IT room C114.
- Any new data cables and any data cables that are moved from the old IT room to the new IT room will need to be documented and tested.
- Single mode fiber will need to be installed between the new IT room C114 and south MultiPurpose Room 115.
- Single mode fiber will need to be installed between the new IT room C114 and VoAg IDF room 206.
- Single mode fiber will need to be installed between the new IT room C114 and Elementary School IDF room A140.
- All fiber will need to terminate in a fiber panel.
- 4-post rack will need to be anchored and installed in the new IT room C114.
- Battery backup will need to be installed in the 4-post rack in the new IT room C114.
- All AP's will need to be installed in each designated classroom.

Scope of work at LaCrosse Elementary School:

- All data cables in the following rooms will be ran to the MDF in the new IT room C114:
  - o A100 A104
  - o A108
  - o A111
  - o A112
  - o A114
  - o A115
  - o A117
  - o A118
  - o A121
- All data cables in the following rooms will be ran to the IDF in room A140:
  - o A123
  - o A128
  - o A130 A134
  - o A136
  - o A145 A146
  - o A150 A151

- o B101 B104
- Elementary school gymnasium AP data cables will be ran to the IDF in room A140.
- All AP's will need to be installed in each designated classroom.
- IDF will need to be installed and mounted.
- Battery backup will need to be mounted and installed in the IDF.